## ADDENDUM 1 TO SALINE COUNTY, HVAC-RETROFIT PACKAGE UNIT AT THE SALINE COUNTY HEALTH DEPT.

## \*\*\*REVISED BID SPECIFICATIONS\*\*\*

Note that the following specifications to the HVAC-Retrofit Package Unit at the Saline County Health Dept. Bid #2017-04-24 have been revised. Bidders should use the revised bid specifications when submitting their bid.

## **SPECIFICATIONS:**

## **HVAC: Retrofit**

Health Dept. 1609 Edison Ave. Benton, AR 72015

Trane Equipment or Equivalent Make/Model: 35 Ton 3 Phase 410a Gas Package Unit

- Hire crane to remove existing 35 ton gas package unit and place new 35 ton gas package unit back in place.
- Install new and complete 35 ton gas package unit into same position as current unit sits.
- Reconnect to gas.
- All necessary duct connections.
- Reconnect to existing vents.
- Pressure system then vacuum to secure no leaks.
- Reconnect to existing ductwork.
- Reconnect electrical and Envision for BACtalk HVAC Control System.
- Start up to insure proper operation.
- Labor and material included.
- Permits included.

Sales and Use Tax: \$	Total Bid Price: \$
Sales and Use Tax: \$	Total Bid Price: \$